



SIKA AT WORK

ONE ST PETER'S SQUARE, MANCHESTER

CONCRETE: Sika® ViscoFlow® 1000 and Sika® Plastiment® 180

BUILDING TRUST



ONE ST PETER'S SQUARE MANCHESTER



The use of Sika concrete admixtures has played a key role in the construction of the 65 metre high central concrete lift shaft at One St Peter's Square, a major new development being built by Carrillion in the centre of Manchester. The 270,000 sq ft BREEAM Excellent (sustainability standard) building will incorporate office space on the upper floors together with an active mix of uses at ground floor level, including cultural space for public exhibitions as well as a stunning double height reception area.

The concrete core, which will incorporate eight lifts, has been constructed using slipform construction. Slipform construction involves vertically raising self-contained formwork on hydraulic jacks, while extruding the reinforced concrete section. It is a fast and cost effective solution suitable for the construction of core walls such as lift shafts in high-rise buildings.

Successful slipform construction relies on a well-designed concrete mix, a skilled workforce and a reliable delivery from the concrete supplier. The concrete needs to have controlled setting to match the rate of climb of the formwork. It requires a soft consistence to obtain full compaction around the steel and give an excellent surface finish but without segregation and grout loss. To retain the excellent surface finish, the concrete also needs to be 'drag free' as it leaves the formwork, eliminating any surface damage caused by friction.


To achieve the correct concrete mix to meet all requirements, Slipform International, specialists in slipform construction working for A J Morrisroe, specialist reinforced concrete and ground work contractors, carried out extensive trials in conjunction with concrete suppliers Hanson Concrete using Sika admixtures.

Dave McFarland of Slipform International said: "The quality of concrete produced and supplied is instrumental in achieving a successful slipform; in other words the key to successful slipforming is in the concrete. With the demand for higher concrete strengths and the associated reduction in the w/c ratio to achieve these strengths plasticising admixtures play a vital role in the production of a quality mix suitable for slipforming. The high slumps and set time needed for pumping and placement require careful selection of the plasticising admixtures and these were established using concrete trials. The trials were carried out both on site and at the plant and the combination of the Sika® ViscoFlow® 1000 superplasticiser and Sika® Plastiment® 180 plasticiser produced a quality concrete that gave both the slump and set time required. This mix was suitably adaptable so that variations in the dosage rate accommodated for changes in the ambient temperature and produced a consistently good concrete finish."

The resulting concrete mix enabled the slipform process to be carried out successfully with a consistent rate of rise of 4.2m per 15 hour shift being achieved. This involved placing up to 160m³ of concrete.

One St Peter's Square, which is designed by Glenn Howells Architects, will contribute to Manchester City Council's £185m redevelopment of the Square, Library Walk, Central Library and Town Hall extension.

For further information call 0800 292 2572.



SIKA LIMITED

Head Office
Watchmead
Welwyn Garden City
Hertfordshire, AL7 1BQ
United Kingdom

Contact

Phone +44 1 707 394444
Fax +44 1 707 329129
Email enquiries@uk.sika.com
www.sika.co.uk
@SikaLimited

BUILDING TRUST

